

INSTITUTE OF ADVANCED STUDY IN SCIENCE AND TECHNOLOGY
AN AUTONOMOUS INSTITUTE UNDER DEPARTMENT
OF SCIENCE AND TECHNOLOGY (GOVT. OF INDIA)
Vigyan path, Paschim Boragaon, Garchuk,
Guwahati – 781 035, India.

Notice Inviting Tender

Advt. No.: 465

Date: 22.12.2023

Sealed Tender are invited from the empaneled contractor of Institute of Advanced Study in Science and Technology, Paschim Boragaon, Guwahati-781035 , for the following works -

Sl. No.	Name of Work	Estimate Amount	Location
1)	Laying of paver block in front site of grocery shop cum canteen at IASST	Rs. 2,67,202.00	Front of Grocery cum Canteen
2)	Approach walkway with paver block to the connecting road with substation	Rs. 89,231.00	Front of Substation
	Grand total	Rs. 3,56,433.00	

The Tender will be received in the office the Registrar of IASST upto 4.00 pm. On 29.12.2023. The tendered price must be valid for one month from the date of acceptance of the tender and no change/ alteration in the tender price is admissible during the period. The Tender price shall be firm and inclusive of all taxes. Details of tenders / terms & conditions can be downloaded from the website of the Institute www.iasst.gov.in

If GST is not included in the quoted price the percentage (%) rate of GST shall be specified in the tender. All other terms and conditions will be as per GCC CPWD-2021 and its subsequent revised editions.

The authority possesses the right to cancel any tender without showing reason thereof.

Encl.....SOR I

Registrar, IASST

Summary of SOR:

A	Total Estimate Value	Rs. 3,56,433.00 (GST Included)
B	Overall % below(-) or above(+) or at par	
C	Total (A+B)	-----
D	GST @12%	Included
E	Grand Total (C) + (D)	-----

(Rupees -----) only

Signature of Bidder

94049/2023/ADMIN-I-IASST

A Estimate for Laying paver block in front of canteen cum grocery shop					
Item No.					
16.3	Supplying and stacking at site				
16.3.1	90 mm to 45 mm size stone aggregate	15	cum	1937.6	29064.00
16.91	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, per direction of Engineer-in-Charge.				
16.91.2	60mm thick cement concrete paver block of M-30 grade	150	Sqm	932.35	139853.00
4.1.8(A)	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :	14.85	cum	4715.60	70027.00
6.26.1	Brick work with common burnt clay machine moulded F.P.S. (non modular) bricks of class designation 12.5 in exposed brick work including making horizontal and vertical grooves 10 mm wide 12 mm deep complete in cement mortar 1:6 (1 cement : 6 coarse sand).	3.00	cum	6849.50	20549.00
2.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.	47.25	cum	107.00	5056.00
13.1.1	Providing 12mm thick plaster on even surface of wall with cement mortar 1:4	9.00	sqm	294.85	2653.65
	Total A				267202.65

A
24.11.2023

Chh
24/11/23

94049/2023/ADMIN-I-IASST

B	Estimate for Laying paver block for Connecting Road to Sub station IASST				
16.3	Supplying and stacking at site				
16.3.1	90 mm to 45 mm size stone aggregate	3.75	cum	1937.6	7266.00
16.91	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, per direction of Engineer-in-Charge.				
16.91.2	60mm thick cement concrete paver block of M-30 grade	37.5	Sqm	932.35	34963.00
4.1.8(A)	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level .	3.375	cum	4715.60	15915.00
6.26.1	Brick work with common burnt clay machine moulded F.P.S. (non modular) bricks of class designation 12.5 in exposed brick work including making horizontal and vertical grooves 10 mm wide 12 mm deep complete in cement mortar 1:6 (1 cement : 6 coarse sand).	3.75	cum	6849.50	25686.00
2.1	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m inwidth or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.	3.75	cum	107.00	401.00
	Miscelenious work	1	job	5000	5000
	Total B			Total	89231.00
	Grand total(A+B)				356433.65

NB .Estimate is prepared as per DSR ,CPWD 2021

24/11/2023

24/11/23