

INSTITUTE OF ADVANCED STUDY IN SCIENCE AND TECHNOLOGY
AN AUTONOMOUS INSTITUTE UNDER DEPARTMENT
OF SCIENCE AND TECHNOLOGY (GOVT. OF INDIA)
Vigyan path, Paschim Boragaon, Garchuk,
Guwahati – 781 035, India.

Notice Inviting Tender

Advt. No.: 509

Date: 03.09.2024

Sealed Tender are invited from the empaneled contractor of Institute of Advanced Study in Science and Technology, Paschim Boragaon, Guwahati-781035, for the following works -

| Sl. No. | Name of Work | Estimate Amount | Location |
|---------|---|--------------------|------------|
| 1 | Renovation of Molecular Biology & Microbial Biotechnology Lab (Room No.138) | 73,532.00 | Lab No.138 |
| 2 | Construction of walk way towards workshop and painting workshop bathroom | 1,03,236.00 | Workshop |
| 3 | Replace of Wooden door frame & wall repairing of KRC at IASST | 1,84,867.00 | KRC |
| | Grand Total | 3,61,635.00 | |

The Tender will be received in the office the Registrar of IASST up to 17.09.2024 on 3.00 pm. The tendered price must be valid for one month from the date of acceptance of the tender and no change/alteration in the tender price is admissible during the period. The Tender price shall be firmed and inclusive of all taxes. Details of tenders / terms & conditions can be downloaded from the website of the Institute www.iasst.gov.in

If GST is not included in the quoted price the percentage (%) rate of GST shall be specified in the tender. All other terms and conditions will be as per GCC CPWD-2021 and its subsequent revised editions.

The authority possesses the right to cancel any tender without showing reason thereof.

Encl.....SOR I

Registrar, IASST

Summary of SOR:1) Renovation of Molecular Biology & Microbial Biotechnology Lab (Room No.138) 2) Construction of walk way towards workshop and painting workshop bathroom & 3) Replace of Wooden door frame & wall repairing of KRC at IASST

| | | |
|----------|--|--|
| A | Total Estimate Value | Rs.3,61,635/ (GST Included) |
| B | Overall% Above or below or at par | ----- |
| C | Total (A+B) | ----- |
| D | GST | Included |
| E | Grand Total (C) + (D) | ----- |

Signature of Bidders

Renovation work of lab no-138

| Item No. | Description of item | Qty | Unit | Rate (Rs) | Amount (Rs) |
|----------|---|--------|------|--------------|------------------|
| 1/13.43 | Apply one coat of cement primer of approved brand and manufacture on plastered surface. | 134.00 | sqm | 64.45 | 8636.30 |
| 2/13.8 | Providing two coats of Birla white wall care puttyof clean water as specified and directed by the department...(Total thickness of two coats is maximum 1.5 mm) | 134.00 | sqm | 123.85 | 16595.90 |
| 3/13.82 | Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. | 134 | sqm | 116.05 | 15550.70 |
| 1 | supply and installation of window blind | 13.875 | sqm | 2000 | 27750.00 |
| 2 | miscelenious job | 1 | job | 5000 | 5000.00 |
| | | | | Total | 73,532.90 |

Name of the Work: - construction of walk way towards workshop and painting of workshop bathroom

| Sl.No- | Description of Item | Unit | Qty | Rate | Amount |
|--------|--|------|-------|---------|-----------|
| 2.8 | Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m inwidth or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. | | | | |
| | All kinds of soil. | Cum | 6.00 | 286.85 | 1,721.10 |
| 4.1.5 | 1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 40 mm nominal sized derived from natural sources) cum | | | | |
| | | Cum | 3.60 | 6833.40 | 24,600.24 |
| 6.1 | Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: 6.1.1 Cement mortar 1:4 (1 cement : 4 coarse sand) cum 6882.00 6.1.2 Cement mortar 1:6 (1 cement : 6 coarse sand) cum 6658.25 | cum | 3.68 | 6658.25 | 24,502.36 |
| 16.68 | Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge | sqm | 20.00 | 951.00 | 19,020.00 |
| 13.43 | Apply one coat of cement primer of approved brand and manufacture on plastered surface. | sqm | 78 | 60.00 | 4,680.00 |

| | | | | | |
|-------|---|--------------|------|----------|-------------------|
| 13.8 | Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. | sqm | 78 | 123.85 | 9,660.30 |
| 13.82 | Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. | sqm | 78 | 116.05 | 9,051.90 |
| | | | | | |
| extra | Misellaneous sanitary item etc | job | 1.00 | 10000.00 | 10,000.00 |
| | | Total | | | 103,235.90 |

Library repairing work

Abstract of cost

| Item No. | Description of Items | Quantity | Unit | Rate | Amount |
|----------|---|----------|------|--------|----------|
| 1/15.56 | Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground | 51 | sqm | 45.05 | 2297.55 |
| 2/22.3 | Providing and laying water proofing treatment to vertical and horizontal surfaces of depressed portions of W.C., kitchen and the like consisting of: | 51 | sqm | 774.25 | 39486.75 |
| 3/13.2 | 15mm thick cement plaster on the rough side of single or half brick wall with cement mortar of 1:4 | 69.00 | sqm | 339.70 | 23439.30 |
| 4/13.85 | Apply one coat of cement primer of approved brand and manufacture on plastered surface. | 72.00 | sqm | 64.45 | 4640.40 |
| 5/13.26 | Providing two coats of Birla white wall care puttyof clean water as specified and directed by the department...(Total thickness of two coats is maximum 1.5 mm) | 72.00 | sqm | 214.3 | 15429.60 |
| 6/13.83 | Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. | 72 | sqm | 121.55 | 8751.60 |
| 7/18.9.9 | Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC | | | | |

| | | | | | |
|----------|--|----|-----|--------------|------------------|
| | solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge | | | | |
| | 100 mm | 24 | mtr | 2811.75 | 67482.00 |
| 8/13.48A | Finishing walls with Acrylic Smooth exterior paint of required shade : | | | | 0.00 |
| | New work (Two or more coat applied @ 1.67 ltr/10 sqm | | | | 0.00 |
| | over and including priming coat of exterior primer applied | 54 | sqm | 154.45 | 8340.30 |
| 9 | Miscelenious item...Door frame change ,anti termite treatment etc.. | 1 | job | 15000 | 15000.00 |
| | | | | Total | 184867.50 |