



INSTITUTE OF ADVANCED STUDY IN SCIENCE AND TECHNOLOGY
AN AUTONOMOUS INSTITUTE UNDER DEPARTMENT
OF SCIENCE AND TECHNOLOGY (GOVT. OF INDIA)
Vigyan path, Paschim Boragaon, Garchuk,
Guwahati – 35

Notice Inviting Tender

Advt. No. 597

Date: 3.07.2026

Sealed Tender are invited from the empanelled contractor of Institute of Advanced Study in Science and Technology, Paschim Boragaon, Guwahati-781035, for the following works -

Sl. No.	Name of Work	Estimate Amount	Location
A	Making Connecting surface drain to Main drain near Engineering cell, IASST	Rs 1,22,131.00	Near Engineering cell
B	Supply, Installation and Commissioning of Chemical Earthing for the Lab No. 122 and 123 (Plasma Nanotech Lab and Dusty Plasma Lab) of IASST	Rs. 73,184.00	Back Side of Lab No. 122 and 123 (Plasma Nanotech Lab and Dusty Plasma Lab)

The Tender will be received in the office the Registrar of IASST up to 3-30 PM on 9.07.2026 and the tender will be opened same day at 4:30 PM. The tendered price must be valid for one month from the date of acceptance of the tender and no change/ alteration in the tender price is admissible during the period. The Tender price shall be firmed and inclusive of all taxes. Details of tenders / terms & conditions can be downloaded from the website of the Institute www.iasst.gov.in

If GST is not included in the quoted price the percentage (%) rate of GST shall be specified in the tender. All other terms and conditions will be as per GCC CPWD-2021 and its subsequent revised editions.

The authority possesses the right to cancel any tender without showing reason thereof.

Encl.....SOR I & II

Registrar, IASST


Summary of SOR I & II:

SOR for the works: (A) Making Connecting surface drain to Main drain near Engineering cell ,IASST” and (B) Supply, Installation and Commissioning of Chemical Earthing for the Lab No. 122 and 123 (Plasma Nanotech Lab and Dusty Plasma Lab) of IASST.

A	Total Estimate Value	₹1,22,131.00 + ₹73,184.00 = ₹1,95,315.00 (GST Included)
B	Overall % above or below or at par	-----
C	Total (A+B)	-----
D	GST	Included
E	Grand Total (C) + (D)	-----

SOR-I

Making Connecting Surface Drain to Main drain Near Engineering cell					
A	SOR				
Sl.No-	Description of Item	Unit	Qty	Rate	Amount
15.59	Dismantling of flexible pavement(paver block) by mechanical means and disposal of dismantled material upto lead a 1 km as per the direction of engineer in-charge	8.00	cum	420.80	3366.40
2.8	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m inwidth or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.	10.00	cum	260.30	2603.00
4.1.5	1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 40 mm nominal sized derived from natural sources) cum	1.05	cum	7294.70	7659.44
6.1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: 6.1.1 * Cement mortar 1:4 (1 cement : 4 coarse sand) cum	5.00	cum	7370.65	36853.25
5.22.6	Steel reinforcement for R.C.C. work including straightening, cutting,	284	kg	107.85	30677.29
4.1	1:1.5:3 (1 Cement: 1.5 coarse sand (zone-III) including manufactured sand derived from Recycled Concrete Aggregate (RCA) upto 25% : 3 graded stone aggregate 20 mm nominal size Recycled Concrete Aggregate (RCA) upto 25%	1.35	cum	8127.00	10971.45
extra	Supply ,fitting and fixing of Hume pipe at approach road for drainaige system	1.00	job	30000.00	30000.00
				Total	122130.82



SOR-II

Name of the Work: Supply, Installation and Commissioning of Chemical Earthing for the Lab No. 122 and 123 (Plasma Nanotech Lab and Dusty Plasma Lab) of IASST

Item No.	Description	Qty		RATE		Amount (In Rupees)
			Unit	Full	Part	
1//	Supply with installation and commissioning of readymade maintenance free CPRI approved Chemical Earthing System with 50mm Dia, 3 Mtr. Length Corrosion free Copper Chemrod Electrode..... inner and outer surface of Brickwall as specified and directed by the department					
		2.00	Each			
	Total	2.00	Each	16838.00	16838.00	₹ 33,676.00
2// 5.14	Providing and fixing 25 mm X 5 mm copper strip on surface or in recess for connections etc. as required.					
		34.00	Mtr			
	Total	34.00	Mtr	1162.00	1162.00	₹ 39,508.00
	Grand total =					₹ 73,184.00
(Rupees Seventy Three Thousand One Hundred Eighty Four Only)						